

# Table of Contents

## 07 — Assumption Ledger

**Project:** Kingsford Hotel Bacolod — **BMS Status:** living document — updated through phases.

ID	Assumption	Rationale	Impact if wrong	Source / phase
A-001	Project is <b>greenfield (new construction)</b> despite cover-letter wording “Rehabilitation”.	Technical inputs are Construction Bulletins against a “For Construction” set, no existing-system inventory, kitchen-layout adjustments. Phase 2 triangulation.	High. Rehab classification would add demolition takeoff, after-hours premiums, cable-reuse evaluation (~P2-4M cost addition).	Phase 2 / Q-001
A-002	<b>Guestroom-floor footprint</b> = ~60 m × 50 m typical floorplate; ~25–35 guestrooms per typical guest floor; ~10 <b>guest</b>	EE-24 Part 1 only shows Basement ↔ 3F; MC Standards references “Roof Deck Level (Guest Room Levels)”; project-scale	Medium. ±20% on guestroom-floor field-device count and corridor cable runs.	Phase 3 / Q-005

ID	Assumption	Rationale	Impact if wrong	Source / phase
	<b>floors above L3, plus roofdeck.</b>	tier (Medium) and Bacolod hotel comparables		
A-003	<b>Equipment counts per system class</b> follow MC Standards typical density × project zoning on BMS-01/02 (e.g., 1× DOAS per floor band, 1× PAHU per landlord-zone, 1× AHU per public area).	Mechanical layouts not in inputs; standard developer practice.	Medium. ±15% on A2 takeoff.	Phase 3 / Q-006
A-004	<b>Full EE drawing set is consistent with CB#8</b> (no contradictions on non-bulletin sheets).	Only revised sheets supplied; latest-issued plan governs.	Low. Revisions affect kitchen power, not BMS bus.	Phase 3 / Q-007
A-005	<b>Upper-floor riser geometry</b>	EE-24 Part 2 missing; standard	Medium. ±15% on inter-floor riser cable lengths.	Phase 3 / Q-008

ID	Assumption	Rationale	Impact if wrong	Source / phase
	<p><b>mirrors typical hotel pattern</b> — single trunk shaft, 1× cable tray per floor for BMS bus + power, ~3.5 m floor-to-floor.</p>	<p>high-rise hotel construction</p>		
A-006	<p><b>BMS-01/02/03 is the complete project-specific BMS sheet set.</b> Hot-water-distribution and in-guestroom BMS scope is <i>not</i> included unless added by addendum.</p>	<p>Only 3 sheets in inputs; no BMS-04 referenced.</p>	<p>Medium. Could re-scope hot-water and guest-floor BMS.</p>	<p>Phase 3 / Q-002</p>
A-007	<p><b>BMS-panel power feed</b> = 1× 20 A, 230 V, 1-phase circuit per BMS panel, supplied and</p>	<p>No BMS feeder named on EE-21/22/23; standard practice.</p>	<p>Low. Power-provision section only.</p>	<p>Phase 3 / Q-009</p>

ID	Assumption	Rationale	Impact if wrong	Source / phase
	<p>terminated by EE Contractor at a knife-disconnect; BMS Contractor terminates downstream</p> <p>.</p>			
A-008	<p><b>Customer GUI / graphics standard</b> per BMS general spec on BMS-01 (per-floor graphics, per-system graphics, summary dashboards, alarm console, trend logs).</p>	<p>No separate GUI standard in inputs; spec already covers GUI requirements.</p>	<p>Low. Refines B2 graphics list.</p>	<p>Phase 3</p>
A-009	<p><b>FAT/SAT protocol</b> per industry standard form (Megaworld-equivalent template), with point-by-point sign-off, PDF</p>	<p>No protocol in inputs.</p>	<p>Low. Scope already inclusive.</p>	<p>Phase 3</p>

ID	Assumption	Rationale	Impact if wrong	Source / phase
	as-built, owner manual binders.			
A-010	<b>Training</b> = 2-day operator-level + 1-day admin/super-user, on-site at handover; 6 trainees × 1 batch.	Not stated; standard inclusion.	Low. Optional row in BOQ.	Phase 3 / Q-016
A-011	<b>M&amp;O after handover</b> = priced as a 1-year preventive maintenance option (4× scheduled visits, 1× annual deep service, 24/7 phone support).	Not stated; offered standalone.	Low. Optional.	Phase 3 / Q-017
A-012	<b>Drawing scale calibration</b> = column grid bay ≈ 7.5 m on EE-03/06/09/12 (mid-range of 6–9 m structural-grid	No explicit scale bar; structural grid recoverable from layouts.	Low–Medium. ±10% on measured cable lengths.	Phase 3 / measure-cable-routes

ID	Assumption	Rationale	Impact if wrong	Source / phase
	hotel/casino bays).			
A-013	<b>Head-end / server location</b> in a central control room on Basement 1 or GF (TBD in coordination); BMS LAN as a standalone backbone with single uplink for off-network reporting.	No room marked; standard hotel BMS pattern.	Low. Affects A5/A6 narrative only.	Phase 3 / Q-011
A-014	<b>Project schedule</b> = 8 months end-to-end (engineering 8 wk, supply lead 12 wk paralleling, install 16 wk, T&C 8 wk, training/handover 2 wk).	No customer schedule stated.	Medium. Drives D1/D2/B4 productivity.	Phase 3 / Q-013
A-015	<b>Commercial terms</b> = 12-month warranty	Industry-standard defaults; not stated.	Variable — affects pricing/cashflow.	Phase 3 / Q-014

ID	Assumption	Rationale	Impact if wrong	Source / phase
	<p>after substantial completion; 30/30/30/10 progress payment; 10% retention released at handover; 12% VAT-inclusive; LD 0.1%/day to cap 10%; no escalation.</p>			
A-016	<p><b>Casino BMS</b> scope (BMS-02 tabulation) is included in BMS Contractor scope (Casino is part of the Kingsford property, not a separate fit-out).</p>	<p>Single proposal request; Casino I/O on the same project-specific points list.</p>	<p>Medium. Could split if Casino is a separate operator.</p>	<p>Phase 3 / Q-003</p>
A-017	<p><b>Fire alarm / security / IT integration</b> is <b>excluded</b> from BMS scope — BMS-only</p>	<p>Not in points list; standard BMS-Contractor scope.</p>	<p>Low. Listed as exclusion.</p>	<p>Phase 3</p>

ID	Assumption	Rationale	Impact if wrong	Source / phase
	HLI to power-meter consumption (per points list), no FDAS/CCTV/access tie-in unless requested.			
A-018	<b>Power monitoring</b> scope = HLI to existing EE meters / sub-meters where Modbus-equipped; no additional power-meter supply by BMS Contractor.	Standard split per MC Standards C/O (Equipment Supplier provides meters; BMS reads HLI).	Low. Scope clarity only.	Phase 3
A-019	<b>Containment</b> (cable tray + conduit) supplied and installed by <b>BMS Contractor</b> for BMS-cabling backbone; trunk-tray sharing with other low-	BMS Contractor scope per “Complete Supply, Delivery, Installation”; consistent with module cabling-and-containment .md.	Medium. ±10% on installation labour.	Phase 3

ID	Assumption	Rationale	Impact if wrong	Source / phase
A-020	voltage allowed where approved. <b>Rate library</b> = _playbook/checklists/standard-pricing-defaults.yaml ml PHP rates with typical 15% spare for cabling and 10% spare for I/O.	Standard rate library; no project-specific quotes received.	Variable — to be refined post-RFQ.	Phase 6

(Additional A-NNN added through Phase 5–10.)